

P.O. Box 14769  
Bredell, 1623

Plot 2/410 Seventh Road  
Bredell A/H, Kempton Park,  
1619

Tel: +27 (0)82 572-2380  
Fax: +27 (0)86 659-2231

Eskom Holdings SOC Ltd  
Majuba Power Station  
**Attention: Mr. Lindani Madonsela**  
Private Bag 9001  
Volkruist  
2470

Date	Your Reference	Our Reference	Enquiries
04 May 2016	Order No.: 4502289115	RCCS247	CC Scheepers Cell: 082 572 2380 e-mail: <a href="mailto:coen@inthuu.co.za">coen@inthuu.co.za</a>

## REPORT – 2016/04/26/RCCS247 PARTICULATE EMISSION MONITOR CORRELATION ON UNIT 2 AT MAJUBA POWER STATION

Herewith the report for the particulate emission monitor correlation measurements carried out between the 01<sup>st</sup> and 03<sup>rd</sup> of April 2016. Tests were carried out on Unit 2 in Stack 1.

We thank you for the opportunity to be of service and trust that your requirements have been interpreted correctly. If you have any queries, please contact us at the above numbers, we will gladly assist.

Yours faithfully  
Inthuu Measurements cc



CC Scheepers



Stack tester <b>AV Makama</b>	Prepared by:  Signature:..... <b>MT Matlou</b>	Issued by:  Signature:..... <b>CC Scheepers</b>
----------------------------------	---	--

# REPORT

**CUSTOMER** : ESKOM MAJUBA POWER STATION

**OPERATING COMPANY** : MAJUBA POWER STATION

**TYPE OF MEASUREMENT** : PARTICULATE EMISSION MONITOR CORRELATION

**TITLE** : PARTICULATE EMISSION MONITOR CORRELATION ON UNIT 2 IN STACK 1 AT MAJUBA POWER STATION

**ORDER No's.** : 4502289115

**REPORT No.** : 2016/04/26/RCCS247

**REPORT DATE** : 04 MAY 2016

COPYRIGHT ON THIS DOCUMENT IS RESERVED. PUBLICATION OR DISSEMINATION OF ITS CONTENTS WITHOUT WRITTEN PERMISSION IS NOT ALLOWED.

# Index

	Page
Index	
Summary	3
Glossary	4
1. Measurement Objective	5
2. Plant Description and Materials Handled	5
3. Description of the Measurement Site	5
4. Measurement and Analytical Methods and Apparatus	6
5. Plant Operating Conditions during the Measurements	6
6. Presentation of Measurement Results and Discussion	6
Appendices	
A. Correlation Function	14
B. Plant Parameters	15
C. Monitor Calibration Certificate	19
D. Recommended Correlation curve	21
7. Distribution list	24

**Summary:**

Plant	:	Majuba Power Station
Operating times	:	24 hours
Emission source	:	Power generation - fossil fuel boilers
Measured components	:	Particulate Matter
Date of measurement	:	01 to 03 April 2016
Emission source No.	:	Unit 2 in Stack 1
Atmospheric Emission Limit	:	100mg/Nm <sup>3</sup> (d) at 10% O <sub>2</sub>

**Measurement results**

1. Nine measurements at 500 MW showed emission concentrations between 15.5 and 28.7 mg/Nm<sup>3</sup> (d) at 10% O<sub>2</sub>
2. PM function as found for AO2,  $y = 25.2564 \cdot mA - 100.8546$
3. PM function as found for AO3,  $y = 9.4711 \cdot mA - 37.7138$
4. PM function recommended for AO2,  $y = 8.2083 \cdot mA - 32.6625$
5. PM function recommended for AO3,  $y = 12.6282 \cdot mA - 50.3419$
6. Gas flow function,  $g = 1.3492 \cdot \text{Total air flow} + 0.9037$

**Where:**

y	=	Particulate emissions	[mg/Nm <sup>3</sup> (d) at 10% O <sub>2</sub> ]
mA	=	Monitor output, AO1 or AO2	[mA]
g	=	Gas flow rate	[Nm <sup>3</sup> /s (d) at 10% O <sub>2</sub> ]
Total air flow			[kg/s]

## GLOSSARY

Some of the following abbreviations were used in the text, figures and Tables:

AMS	Automated Measurement System
SRM	Standard Reference Method
CEM	Continuous Emission Monitor
ESP	Electrostatic Precipitator
FFP	Fabric Filter Plant
MCR	Maximum Continuous Rating
°C	Degrees Celsius
Pa (g)	Gauge pressure in Pascal
kPa (abs)	Absolute pressure in kilo Pascal
% v/v	Percentage on a Volume-by-Volume basis
Am <sup>3</sup>	<b>Actual</b> Cubic Metres
Nm <sup>3</sup>	<b>Normal</b> Cubic Metres
Am <sup>3</sup> (w)	<b>Actual</b> Cubic Metres on a wet basis
Nm <sup>3</sup> (w)	<b>Normal</b> Cubic Metres on a wet basis
Am <sup>3</sup> (d)	<b>Actual</b> Cubic Metres on a dry basis
Nm <sup>3</sup> (d)	<b>Normal</b> Cubic Metres on a dry basis
ATPD	Actual Temperature and Pressure – Dry
NTPD	Normalised Temperature and Pressure - Dry
g/s	Grams per second
mg/s	Milligrams per second
dP	Differential pressure
AO	Analogue Output

- **'Actual'** refers to the measured temperature and pressure conditions of the gases in the duct.
- **'Normal' or 'Standard'** refers to the actual conditions being normalised to 0 °C and 101,325 kPa.

## **1 MEASUREMENT OBJECTIVE**

Inthuu Measurements CC was contracted by Majuba Power Station, to perform the Particulate Emission Monitor correlation from which monthly reports are generated.

The objective was to determine a linear regression allowing the reporting of emissions from an Automated Measurement System (AMS). Constants are derived from the gravimetric measurements by a Standard Reference Method (SRM) and the corresponding AMS signal.

The correlation function must report emissions at normal running condition, but must at the same time be able to indicate excursions over the Ambient Emission Limit when plant problems occur.

Tests were carried out between the 01<sup>st</sup> and 03<sup>rd</sup> of April 2016.

## **2 PLANT DESCRIPTION AND MATERIALS HANDLED**

The power station currently operates six power generation units, each consisting of a steam driven turbine and a boiler supplying the steam. The boilers are specially designed to burn low grade coal, which contains high percentages of ash and sulphur.

Each unit is equipped with particulate matter abatement technology. Majuba uses Fabric filters (FFPs) to clean the boiler waste gases. Currently, no further emission abatement technology is implemented at Majuba Power Station.

## **3 DESCRIPTION OF THE MEASUREMENT SITE**

The measuring site is located inside the multi-flue stack.

The stack consists of a concrete outer windshield with three flues inside the windshield. The height of the 250m tall stack is divided into 8 levels, level 8 being the last platform before the "roof" of the stack. Each level is a concrete slab through which the three flues enter from the bottom. The bottom flue fits into the flue above it without significant flow disturbance. The flue above each level is supported by that level. This arrangement allows for the expansion and contraction of the flue of one unit without being influenced by the other flues when one of the boilers is switched on or off. Expansion and contraction of the flues do not influence the level of the concrete floor.

The ports are positioned at a height above the floor so that neither the ports nor the alignment of the instruments are influenced by the expansion and contraction of the flue. The alignment of the monitors is therefore very stable. The particulate AMS is situated on the fourth level. In Stack 1 (Units 1, 2 and 3), the sampling ports are situated on level 8. In Stack 2 (Units 4, 5 and 6), the ports are situated on the sixth level.

The three flues being encompassed by the wind shield require the use of one probe of 9.5m to traverse one complete diameter (Traverses A and B) and another 3.5m probe to traverse the two radii (traverses B and C) at 90° to traverses A and B.

The sampling ports being situated on the very top level in Stack 1, made it impossible to rig the 9.5m probe onto the measuring platform. It was agreed with the customer to perform three out of four traverses on the flues of Units 1, 2 and 3.

#### 4 MEASUREMENT AND ANALYTICAL METHODS AND APPARATUS

Compound	Method	Comment
Particulate Matter	BS EN 9096:2003	-
Low mass concentrations	BS EN 13284-1:2002	-
Correlation function	VDI 2066, Part 4	Statistical procedures for establishing confidence and tolerance bands
Eskom's Emissions Monitoring and Reporting Standard	240-56242363	-

#### 5 PLANT OPERATING CONDITION DURING THE MEASUREMENTS

Normal operating conditions were maintained for the duration of the emission survey. The tests were carried out at a constant load for the full duration of nine consecutive tests for 3 days. Low, Mid and High loads were arranged to achieve a spread in the emission concentrations. The low and mid loads were arranged for the weekend, but Majuba was experiencing wet coal and they couldn't load further. The poor performance of mills further contributed to the inability to increase load.

The tests were carried out at a condition which represents the normal state of power production. The coal which was burnt during the test period was the normal supply.

The economiser outlet oxygen levels were representative of normal running excess air levels. Air ingress, in the form of in-leakage, may be expected at the air heaters and the FFPs under normal running conditions. The FFP bags are protected against high temperatures by an attemperating system, which allows ambient air into the main gas stream to cool the flue gas down. No abnormal ingress air was noticed from the O<sub>2</sub> readings in the stack.

Additional operating data is tabulated in the Appendices.

#### 6 PRESENTATION OF MEASUREMENT RESULTS AND DISCUSSION

##### 6.1 EVALUATION OF THE OPERATING CONDITIONS DURING THE MEASUREMENTS

It is an Eskom standard that, if it is not possible to vary the loads, that the correlation tests are carried out at a load most commonly experienced. Tests are carried out without soot blowing and oil support in each case.

Below is a summary of the main relevant plant and test parameters.

Test No.	Actual Boiler load during test	Load condition	Measured Gas flow	Total Air flow	Standard deviation of air flow	Dust Concentration	Average face velocity	% Isok	Nozzle diameter	Comment
	MW	-	[Am <sup>3</sup> /s (d)] at 10% O <sub>2</sub>	[kg/s]	kg of Total Air flow	mg/Nm <sup>3</sup> (d) at 10% O <sub>2</sub>	cm/s	%	mm	
1	500.00	80% MCR	1308.5	588.8	14.0	20.5	3.86	98.0	4.2	
2	500.00	80% MCR	1439.7	620.3	9.7	21.7	4.23	98.6	4.2	
3	500.00	80% MCR	1389.1	599.7	8.4	21.8	4.12	98.5	4.2	
4	500.00	80% MCR	1370.4	581.0	13.1	15.5	4.04	96.9	4.2	
5	500.00	80% MCR	1386.8	584.9	6.9	28.7	4.08	98.7	4.2	Not included
6	500.00	80% MCR	1425.0	585.1	8.9	17.6	4.12	97.6	4.2	
7	500.00	80% MCR	1374.1	591.8	7.3	18.1	4.03	99.2	4.2	
8	500.00	80% MCR	1363.2	577.3	5.2	17.2	4.01	98.7	4.2	
9	500.00	80% MCR	1364.7	583.0	16.1	17.3	4.00	99.0	4.2	

All the face velocities were above 3 cm/s specified in the Eskom Standard

The isokineticities were all between the 95 – 105% as per the allowed range in the Eskom Standard. Test 5 was not included in the linear regression. The test falls outside the tolerance bands for this correlation. Test error is expected. Due to the low emissions, it was not possible to know from the available information whether the final dust concentration was acceptable or not and consequently Test 5 was not repeated. It was considered unnecessary to conduct further tests, since all eight the other tests were carried out at the same load.

## 6.2 MEASUREMENT RESULTS

One test was omitted from the calculations. The correlation function was determined from eight parallel measurements.

The function yields the emission in mg/Nm<sup>3</sup> (d) at 10% O<sub>2</sub> corrected for temperature, pressure, moisture and oxygen.

The following table gives the pertinent monitor information and correlation parameters for the “as found” conditions.

<b>Plant:</b>	<b>Unit 2</b>	
Location of Monitor	Stack 1	
Make:	SICK	
Model:	DHT200	
Monitor serial number:	12068626/12068634	
Reflector serial number:	12068602	
Channel	<b>Analogue Output AO 2:</b>	<b>Analogue Output AO 3:</b>
Measuring range (mg/m <sup>3</sup> )	0.0 - 0.8	0.0 - 0.3
DCS measuring range (mg/Nm <sup>3</sup> ) at 10 %O <sub>2</sub>	404.3	151.7
Output range (mA):	4 - 20	4 - 20
<b>Info for DCS</b>		
	mA	Emission
	4.00	0.2
	5.97	50.0
	9.26	133.0
	20.00	404.3
	% Output	Emission
	0.00	0.2
	12.33	50.0
	100.00	404.3
<b>Constants for Linear function (mA)</b>		
	m <sub>mA</sub> =	25.2564
	c <sub>mA</sub> =	-100.85
<b>Constants for Linear function (%)</b>		
	m <sub>%</sub> =	4.0410
	c <sub>%</sub> =	0.1708

Detailed results from the sampling process:

Test No.		1	2	3
Stack tester:		AVM	AVM	AVM
Date	dd-mm-yy	2016-04-01	2016-04-01	2016-04-01
Start Time	HH:mm	11H00	13H59	15H37
End Time	HH:mm	12H24	15H13	16H46
Boiler load	MW	500	500	500
<b>Outlet Conditions.</b>				
Gas Temperature	°C	107.6	112.7	107.7
Barometric pressure	kPa (g)	81.1	80.7	80.5
Duct pressure	kPa (abs)	80.8	80.5	80.4
Moisture	%v/v	5.5	4.9	5.9
Oxygen (O2)	%	8.6	8.6	8.6
Velocity	m/s	23.45	25.64	24.99
Duct area	m2	52.43	52.43	52.43
Gas Volume Flow (Qact)	Am3/s	1229.44	1344.23	1310.35
Gas Volume Flow (Qad 10 %O2)	Am3/s	1308.48	1439.70	1389.11
Gas Volume Flow (Qnd 10 %O2)	Nm3/s	748.83	810.11	790.28
Gas flow rate	kg/s	900.13	965.06	954.27
Sampling time	Minutes	60	60	60
Dust mass	mg	14.31	16.49	16.13
Gas Volume Sampled (Vnd)	Nm3 (d)	0.6200	0.6745	0.6572
Dust Concentration	mg/Nm3 (d)	23.1	24.5	24.5
Correction factor 10%		0.9	0.9	0.9
Dust Concentration Normalised to 10% O2	mg/Nm3 (d) @ 10% O2	20.5	21.7	21.8
Outlet Dust Flowrate	mg/s	15343.4	17585.6	17224.1
Moisture Concentration	g/Nm3 (d)	46.8	41.5	50.2
Average Face velocity	cm/s	3.9	4.2	4.1
Isokineticity	%	98.0	98.6	98.5
Average O/M Signal AO1	mA of output	4.87	4.96	4.93
Average O/M Signal AO1	% of output	5.44	5.98	5.79
AO1 Ext range		0.70		
Measured Extinction	Ext	0.0380	0.0419	0.0405
AO2 Ext range		0.80		
Average O/M Signal AO2	mA of output	4.76	4.84	4.81
Average O/M Signal AO2	% of output	4.76	5.23	5.06



Test No.		4	5	6
Stack tester:		AVM	AVM	AVM
Date	dd-mm-yy	2016-04-02	2016-04-02	2016-04-02
Start Time	HH:mm	9H15	10H40	12H04
End Time	HH:mm	10H24	11H45	13H09
Boiler load	MW	500	500	500
<b>Outlet Conditions.</b>				
Gas Temperature	°C	102.2	104.3	107.1
Barometric pressure	kPa (g)	81.0	80.9	80.9
Duct pressure	kPa (abs)	80.9	80.8	80.7
Moisture	%v/v	6.1	6.8	5.9
Oxygen (O2)	%	8.5	8.4	8.3
Velocity	m/s	24.51	24.80	25.04
Duct area	m2	52.43	52.43	52.43
Gas Volume Flow (Qact)	Am3/s	1284.97	1300.27	1312.65
Gas Volume Flow (Qad 10 %O2)	Am3/s	1370.45	1386.79	1424.97
Gas Volume Flow (Qnd 10 %O2)	Nm3/s	796.03	800.18	815.84
Gas flow rate	kg/s	957.81	954.54	956.40
Sampling time	Minutes	60	60	60
Dust mass	mg	11.41	21.52	13.33
Gas Volume Sampled (Vnd)	Nm3 (d)	0.6463	0.6563	0.6567
Dust Concentration	mg/Nm3 (d)	17.7	32.8	20.3
Correction factor 10%		0.9	0.9	0.9
Dust Concentration Normalised to 10% O2	mg/Nm3 (d) @ 10% O2	15.5	28.7	17.6
Outlet Dust Flowrate	mg/s	12376.2	22928.7	14358.4
Moisture Concentration	g/Nm3 (d)	51.8	58.7	50.2
Average Face velocity	cm/s	4.0	4.1	4.1
Isokineticity	%	96.9	98.7	97.6
Average O/M Signal AO1	mA of output	4.76	4.88	4.95
Average O/M Signal AO1	% of output	4.77	5.52	5.97
AO1 Ext range				
Measured Extinction	Ext	0.0334	0.0387	0.0418
AO2 Ext range				
Average O/M Signal AO2	mA of output	4.67	4.77	4.84
Average O/M Signal AO2	% of output	4.17	4.83	5.22

Test No.		7	8	9
Stack tester:		AVM	AVM	AVM
Date	dd-mm-yy	2016-04-03	2016-04-03	2016-04-03
Start Time	HH:mm	9H25	10H50	12H16
End Time	HH:mm	10H33	11H57	13H25
Boiler load	MW	500	500	500
<b>Outlet Conditions.</b>				
Gas Temperature	°C	96.5	99.5	98.5
Barometric pressure	kPa (g)	81.6	81.6	81.6
Duct pressure	kPa (abs)	81.5	81.5	81.5
Moisture	%v/v	6.2	6.0	6.4
Oxygen (O <sub>2</sub> )	%	8.4	8.5	8.4
Velocity	m/s	24.49	24.36	24.30
Duct area	m <sup>2</sup>	52.43	52.43	52.43
Gas Volume Flow (Q <sub>act</sub> )	Am <sup>3</sup> /s	1283.75	1277.10	1274.14
Gas Volume Flow (Q <sub>ad</sub> 10 %O <sub>2</sub> )	Am <sup>3</sup> /s	1374.15	1363.16	1364.75
Gas Volume Flow (Q <sub>nd</sub> 10 %O <sub>2</sub> )	Nm <sup>3</sup> /s	816.81	803.27	806.42
Gas flow rate	kg/s	970.65	956.75	958.20
Sampling time	Minutes	60	60	60
Dust mass	mg	13.95	12.94	13.16
Gas Volume Sampled (V <sub>nd</sub> )	Nm <sup>3</sup> (d)	0.6756	0.6643	0.6639
Dust Concentration	mg/Nm <sup>3</sup> (d)	20.6	19.5	19.8
Correction factor 10%		0.9	0.9	0.9
Dust Concentration Normalised to 10% O <sub>2</sub>	mg/Nm <sup>3</sup> (d) @ 10% O <sub>2</sub>	18.1	17.2	17.3
Outlet Dust Flowrate	mg/s	14775.6	13778.6	13966.8
Moisture Concentration	g/Nm <sup>3</sup> (d)	53.3	51.2	55.0
Average Face velocity	cm/s	4.0	4.0	4.0
Isokineticity	%	99.2	98.7	99.0
Average O/M Signal AO1	mA of output	4.75	4.72	4.75
Average O/M Signal AO1	% of output	4.70	4.50	4.66
AO1 Ext range				
Measured Extinction	Ext	0.0329	0.0315	0.0326
AO2 Ext range				
Average O/M Signal AO2	mA of output	4.66	4.63	4.65
Average O/M Signal AO2	% of output	4.11	3.94	4.08

Detailed information is given in the Appendices:

**Appendix A – Figures**

1. Emission Monitor Correlation Certificate [Normal dry at 10 %O<sub>2</sub>]
2. Stack Gas Flow Correlation Certificate [Normal dry at 10 %O<sub>2</sub>]

**Appendix B – Plant parameters**

**Appendix C – Monitor calibration certificates**

**Appendix D – Correlation functions and parameters**

# **APPENDIX A**

## **Correlation Function**

Figure 1 – As found

Figure 2 – Air to gas flow correlation

# MAJUBA POWER STATION

## Emission Monitor Correlation Certificate

**Plant:** Unit 2  
**Location of monitor:** Stack 1

**Monitor information:**

Make of Monitor: Sick  
 Model: DHT200

**Serial Numbers:**  
 Optical head: 12068626/12068634  
 MCU 12068602

**Limits of validity:**

Lower limit 15.55 mg/Nm<sup>3</sup> (d) [as an hourly average]  
 Upper limit 21.79 mg/Nm<sup>3</sup> (d) [as an hourly average]

**Operational data:**

Path length: N/A mm [Stack flange to Stack flange]  
 Monitor range: 4 - 20 mA  
 Analogue Output AO 2: 0.0 - 0.8 mg/m<sup>3</sup>  
 Analogue Output AO 3: 0.0 - 0.3 mg/m<sup>3</sup>

Measuring Range: 0.8 - 404.3 mg/Nm<sup>3</sup> at 10 %O<sub>2</sub>  
 Measuring Range: 0.3 - 151.7 mg/Nm<sup>3</sup> at 10 %O<sub>2</sub>  
 AEL Limit 100 mg/Nm<sup>3</sup> @ 10% O<sub>2</sub>


**Dates:**

Calibration date: 09-Feb-16  
 Correlation dates: 01-03 April 2016

mA	Analogue Output AO 2:	Analogue Output AO 3:
4.00	0.2	0.2
7.95	100.0	37.6
14.54	266.4	100.0
20.00	404.3	151.7

**Linear function:**

$E_{AO2} = 25.2564x - 100.8546$       Correlation coefficient(R) = 0.99  
 $E_{AO3} = 9.4711x - 37.7138$   
 where: E = Emission [mg/Nm<sup>3</sup>(d)@ 10% O<sub>2</sub>]  
 x = Monitor output [mA]



**FIGURE 1**

Prepared by: Inthuu Measurements

## MAJUBA POWER STATION

### Stack Gas Flow Correlation Certificate

**Plant:** Unit 2

**Location of monitor:** Stack 1

**Monitor information:**

Make of Monitor: Sick

Model: N/A

**Serial Numbers:**

N/A

N/A

**Limits of validity:**

Lower limit 748.38 Nm<sup>3</sup>/s (d) at 10 %O<sub>2</sub> [as an hourly average]

Upper limit 816.81 Nm<sup>3</sup>/s (d) at 10 %O<sub>2</sub> [as an hourly average]

**Operational data:**

Stack internal diameter 8.1702 m

Monitor range: N/A -

**Dates:**

Calibration date: N/A

Correlation dates: 01 - 03 April 2016

**Linear function:**

$$g = 1.3492a + 0.9037$$

Correlation coefficient(R) = 1.00

where: g = Stack exit gas flow [Nm<sup>3</sup>/s (d) at 10 % O<sub>2</sub>]

a = Total air flow from DCS [Kg/s]




FIGURE 2

Prepared by: Inthuu Measurements

# **APPENDIX B**

## **Plant Parameters**

Plant parameters for the duration of the tests:

Test No.	1	2	3
Stack tester:	AVM	AVM	AVM
Date	2016-04-01	2016-04-01	2016-04-01
Start Time	11H00	13H59	15H37
End Time	12H24	15H13	16H46
Boiler load	500	500	500
<b>Outlet Conditions.</b>			
SO2 EMISSION	669.79	674.47	694.93
NOX EMISSION	523.37	541.57	542.91
DUCT PRESSURE	826.51	824.24	823.98
LH AFT ATT AVE T	113.80	117.56	111.09
RH AFT ATT AVE T	107.68	112.30	105.67
DUST EMISSION	4.94	5.42	5.31
MAX MAIN DIFF PRESS	1.75	1.96	1.81
FFP PLANT RUNNING H	72.16	75.04	76.65
CELLS IN SERVICE	8.00	8.00	8.00
PLSAIR SUPPLY PRESS.	74.97	75.08	74.99
BLOW OFF CTRL VLV	78.85	74.12	76.36
TARGET LD SET POINT	500.00	500.00	500.00
UPPER LOAD LIMIT	500.00	500.00	500.00
LOWER LOAD LIMIT	400.00	400.00	400.00
DUST IN MG/SM3	6.20	6.79	6.67
DUST VELOCITY	23.80	25.22	24.18
BLR LOAD DEM	500.00	500.00	500.00
LH A/H OUT F/GAS T	116.85	120.74	114.36
LH A/H OUT F/GAS T	116.75	120.52	113.40
TOTAL FUEL FLOW	67.38	85.35	81.17
ML MAIN MTR KW	0.00	0.00	0.00
GENERATOR MW	503.59	503.35	503.95
O2 CONTROL RATIO	0.36	-0.13	0.14
LH A/H INL F/GAS O2	4.08	4.49	4.04
LH ID FAN IN F/GAS T	111.47	114.71	109.71
RH A/H INL F/GAS O2	3.85	4.36	3.88
RH ID FAN IN F/GAS T	105.32	108.98	103.99
TOTAL AIR FLOW	588.84	620.26	599.68
FUEL/AIR SET POINT	0.90	0.77	0.79
TOTAL FEED WATER F	417.71	414.44	415.33



Test No.	4	5	6
Stack tester:	AVM	AVM	AVM
Date	2016-04-02	2016-04-02	2016-04-02
Start Time	9H15	10H40	12H04
End Time	10H24	11H45	13H09
Boiler load	500	500	500
<b>Outlet Conditions.</b>			
SO2 EMISSION	701.90	719.52	725.01
NOX EMISSION	521.43	533.59	536.83
DUCT PRESSURE	827.25	827.49	826.76
LH AFT ATT AVE T	108.99	110.77	113.08
RH AFT ATT AVE T	103.24	105.27	108.02
DUST EMISSION	4.36	5.07	5.46
MAX MAIN DIFF PRESS	1.72	1.77	1.83
FFP PLANT RUNNING H	94.31	95.67	97.06
CELLS IN SERVICE	8.00	8.00	8.00
PLSAIR SUPPLY PRESS.	74.94	75.09	75.00
BLOW OFF CTRL VLV	79.29	76.81	72.84
TARGET LD SET POINT	500.00	500.00	500.00
UPPER LOAD LIMIT	500.00	500.00	500.00
LOWER LOAD LIMIT	400.00	400.00	400.00
DUST IN MG/SM3	5.44	6.36	6.86
DUST VELOCITY	23.39	23.60	23.72
BLR LOAD DEM	500.00	500.00	500.00
LH A/H OUT F/GAS T	112.20	113.74	116.46
LH A/H OUT F/GAS T	111.76	113.47	115.96
TOTAL FUEL FLOW	79.21	81.97	84.02
ML MAIN MTR KW	0.00	0.00	0.00
GENERATOR MW	504.33	502.81	504.29
O2 CONTROL RATIO	-0.13	-0.12	0.01
LH A/H INL F/GAS O2	3.87	3.86	3.78
LH ID FAN IN F/GAS T	106.20	107.98	110.14
RH A/H INL F/GAS O2	3.72	3.72	3.58
RH ID FAN IN F/GAS T	100.22	102.20	105.02
TOTAL AIR FLOW	580.97	584.93	585.11
FUEL/AIR SET POINT	0.83	0.81	0.79
TOTAL FEED WATER F	406.57	407.66	413.54

Test No.	7	8	9
Stack tester:	AVM	AVM	AVM
Date	2016-04-03	2016-04-03	2016-04-03
Start Time	9H25	10H50	12H16
End Time	10H33	11H57	13H25
Boiler load	500	500	500
<b>Outlet Conditions.</b>			
SO2 EMISSION	712.10	700.08	675.06
NOX EMISSION	520.51	505.11	500.14
DUCT PRESSURE	833.75	833.57	832.92
LH AFT ATT AVE T	102.63	103.86	104.30
RH AFT ATT AVE T	97.31	98.31	98.98
DUST EMISSION	4.34	4.24	4.39
MAX MAIN DIFF PRESS	1.64	1.57	1.66
FFP PLANT RUNNING H	118.45	119.86	121.32
CELLS IN SERVICE	8.00	8.00	8.00
PLSAIR SUPPLY PRESS.	74.97	75.02	75.09
BLOW OFF CTRL VLV	82.77	81.24	80.16
TARGET LD SET POINT	500.00	500.00	500.00
UPPER LOAD LIMIT	500.00	500.00	500.00
LOWER LOAD LIMIT	400.00	400.00	400.00
DUST IN MG/SM <sup>3</sup>	5.45	5.33	5.51
DUST VELOCITY	23.36	22.96	23.20
BLR LOAD DEM	500.00	500.00	500.00
LH A/H OUT F/GAS T	105.53	107.54	107.77
LH A/H OUT F/GAS T	104.48	106.36	106.70
TOTAL FUEL FLOW	82.82	82.41	83.92
ML MAIN MTR KW	0.00	0.00	0.00
GENERATOR MW	501.84	502.67	496.83
O2 CONTROL RATIO	-0.22	0.12	-0.08
LH A/H INL F/GAS O2	4.18	3.92	4.10
LH ID FAN IN F/GAS T	100.09	101.66	102.19
RH A/H INL F/GAS O2	4.02	3.63	3.79
RH ID FAN IN F/GAS T	94.90	96.16	96.76
TOTAL AIR FLOW	591.81	577.31	582.98
FUEL/AIR SET POINT	0.81	0.79	0.79
TOTAL FEED WATER F	408.81	409.40	408.22

# **APPENDIX C**

## **Monitor Calibration certificate**


## Electronic Calibration Certificate:

### DHT200

<b>Customer data:</b>	<b>Certificate:</b>	<b>T200-EC02-09022016-RM002</b>
Customer: Eskom Majuba	Customer no:	
Country: South Africa	City:	
Plant: Majuba	Location: Stack 1 (Unit 2)	

<b>1. Device data:</b>			
Device type :	DHT200	Device type MCU:	NW0DNO 1000 NNNE
Serial no:	12068626/12068634	Serial No:	12068602
Firmware no. :	01.08.14/01.02.01	Firmware no. MCU:	01.06.00
Measuring Units:	Ext	AO Measuring Range AO1/AO2/AO3:	0.7/0.8/0.3

<b>2. Filter linearity Check: SN: 0-T059 – 80-T059</b>			
Filter [%]	Measured value [%]	Deviation [%]	Allowable deviation [%]
83.3	82.9	-0.4	2.0
58.9	58.7	-0.2	2.0
38.1	37.6	-0.5	2.0
20.5	20.3	-0.2	2.0
0.0	-0.3	-0.3	2.0

<b>Remarks:</b>			
Date :	09-02-2016	Name:	Signed:
Valid until:	09-02-2017	Engineer: Reentseng Molapo	

# **APPENDIX D**

## **RECOMMENDED CORRELATION CURVE**

# MAJUBA POWER STATION

## Emission Monitor Correlation Certificate

**Plant:** Unit 2  
**Location of monitor:** Stack 1

**Monitor information:**

Make of Monitor: Sick  
 Model: DHT200  
Serial Numbers:  
 Optical head: 12068626/12068634  
 MCU 12068602

**Limits of validity:**

Lower limit 15.55 mg/Nm<sup>3</sup> (d) [as an hourly average]  
 Upper limit 21.79 mg/Nm<sup>3</sup> (d) [as an hourly average]  
 Hourly cycle checks are included in linear regression

**Operational data:**

Path length: N/A mm [Stack flange to Stack flange]  
 Monitor range: 4 - 20 mA  
 Analogue Output AO 2: 0.0 - 0.26 mg/m<sup>3</sup>      Measuring Range: 0.26 - 131.5 mg/Nm<sup>3</sup> at 10 %O<sub>2</sub>  
 Analogue Output AO 3: 0.0 - 0.4 mg/m<sup>3</sup>      Measuring Range: 0.4 - 202.2 mg/Nm<sup>3</sup> at 10 %O<sub>2</sub>  
 AEL Limit 100 mg/Nm<sup>3</sup> @ 10% O<sub>2</sub>


**Dates:**

Calibration date: 09-Feb-16  
 Correlation dates: 01-03 April 2016

mA	Analogue Output AO 2:	Analogue Output AO 3:
4.00	0.2	0.2
16.16	100.0	153.8
11.91	65.1	100.0
20.00	131.5	202.2

**Linear function:**

$E_{AO2} = 8.2083x - 32.6625$       Correlation coefficient(R) = 0.99  
 $E_{AO3} = 12.6282x - 50.3419$   
 where: E = Emission [mg/Nm<sup>3</sup>(d)@ 10% O<sub>2</sub>]  
 x = Monitor output [mA]



**FIGURE 3**

Prepared by: Inthuu Measurements

<b>Plant:</b>	<b>Unit 2</b>	
Location of Monitor	Stack 1	
Make:	SICK	
Model:	DHT200	
Monitor serial number:	12068626/12068634	
Reflector serial number:	12068602	
Channel	<b>Analogue Output AO 2:</b>	<b>Analogue Output AO 3:</b>
Measuring range (mg/m <sup>3</sup> )	0.0 - 0.26	0.0 - 0.4
DCS measuring range (mg/Nm <sup>3</sup> ) at 10 %O <sub>2</sub>	131.5	202.2
Output range (mA):	4 - 20	4 - 20
<b>Info for DCS</b>		
mA	Emission	Emission
4.00	0.2	0.2
10.07	50.0	76.8
7.95	32.6	50.0
20.00	131.5	202.2
% Output	Emission	Emission
0.00	0.2	0.2
37.94	50.0	76.8
100.00	131.5	202.2
<b>Constants for Linear function (mA)</b>		
$m_{mA} =$	8.2083	12.6282
$c_{mA} =$	-32.66	-50.34
<b>Constants for Linear function (%)</b>		
$m_{\%} =$	1.3133	2.0205
$c_{\%} =$	0.1708	0.1708

**7 DISTRIBUTION LIST**

L Madonsela  
CC Scheepers

Majuba Power Station - BPE  
Inthuu Measurements CC